GENERAL NOTES:

- Unless specifically waived, the Developer shall comply with Chapter 13 (Landscaping, Tree Removal, and Site Clearing) of the City of Tampa Code.
- The Developer shall comply with the requirements of the City of Tampa Code and SWFWMD Chapter 40D-4, 40, 400 F.A.C. regarding stormwater management. The Developer will connect the project's stormwater system to the City of Tampa system at their cost (may involve crossing Franklin Street no current system exists on vest side of street).
- 3. The compactor room will be no less than 15' across x 35' deep with a minimum 15' width door opening (these are inside, open space, measurements). The dimensions are drawn to scale on the site plan. The compactor will be located within a room by itself with an overhead roll up door. This door will be open only during the times of service to the compactor. The compactor will be on a 4'5' high dock/platform installation and operation of a winch system will enable service. The vertical clearance of 16 will be at both OH. Hord up doors (first to enter the building/service area and second to the compactor room), within the entire service area, and within the compactor room.
- 4 The Developer shall comply with the requirements of the City of Tampa Fire Codes applicable to the project at time of permitting.
- 5. All structures will meet the required site distance per City of Tampa Code Sec 27-240 for visibility at
- The Developer will comply with the parking requirements of the City of Tampa Code applicable to the project at the time of permitting
- 7. The Developer shall coordinate with the Department of Public Works regarding the placement of sidewalks along the adjoining public right-of-way. The Developer shall provide at a minimum, 15 sidewalks adjacent to North Frankin Street, East Twiggs Street, and East Zack Street and 141 sidewalks adjacent to North Frankin Street within the City of Tempa and FDOT rights of way, adjacent to
- 8. The Developer shall comply with the City of Tampa Transportation Division Technical Standards.
- 9 All driveways are subject to final approval by the City Transportation Division
- All proposed vegetation in the public right-of-way is conceptual and subject to the approval of the City Transportation Division.
- 11. The Developer shall coordinate with the City Transportation Division and the City Parks and Recre. Department, Planning and Design Division to provide appropriate pedestrian cross walks and pedes signalization for the pedestrian sidewarks, where appropriate.
- 12. Appropriate bicycle parking shall be provided pursuant to City of Tampa Code Chapter 27-324.
- 13. All facades of the parking garage shall be screened and architecturally integrated into the primary building in a manner consistent with the standards contained in Article XVIII, "Central Business District" of Chapter 27 of the City Codes as determined by the city's Urban Design Manager. If the screening and treatment of the facades of the parking garage are not approved by the Urban Design Manager, then it shall constitute a substantial change and shall be subject to review by the City Council.
- 14. The applicant will meet the CBD open space requirements.
- 15. The applicant will meet the CBD public art requirement (Section 27-441(2)(d)).
- All streetscaping vegetation along all adjacent roads must be approved by the City Parks & Recreation Department.
- To ensure conformance to the CBD standards, the site plan will be subject to 30%, 60%, and 90% design review by the Urban Design Manager.
- Streetscape maintenance agreements should be in place prior to issuance of certificates of occupancy for any phase of construction.
- 19 On Franklin Street, the Developer will assure that maxicom cabling, wiring, and the electrical panel associated with the streetscaping will remain intact. Any damages due to construction will be repaired.
- 20. Maintenance agreements should be in place prior to issuance of certificate of occupancy for any phase
- 21. On Franklin Street, the Developer will assure that maxicom cabling and wiring will remain intact. Any damages due to construction will be repaired at the Developer's expense in a timely fashion.
- 23. Approved uses within the project are contemplated to include wet zoning approval for sale of alcot beverages. Such wet zoning proposals will be brought to the City Council for consideration undersearate wet zoning application.
- Permitted uses within the commercial portion of the development shall include all commercial general uses, including office.
- 25. All driveway exits shall have stop signs and pedestrian crossing signs.
- 28. Pursuant to the Development Order conditions for the Downtown DRI, as amended, this project must perform an archaeological assessment prior to or at the time of demolition of any existing structure or stab, or if the site is currently cleared, prior to the foundation permit. Demolition permits another foundation permits will not be issued until such time as either the site has received its archaeologisal assessment or proof that an archaeologist has been retained for subsequent analysis, with said proof being provided to the City of Tampa Land Development Coordination Office. The final archaeological assessment must be provided to the City of Tampa prior to release of the Certificate of Occupancy.
- 27. The open space areas located at the following locations: 1) at the corner of Zeck and Frankin; 2) along Zeck Street; 3) along Frankin Street; and 4) along Twiggs Street; shall be activated through the use of direct connections with the interior commercial space.
- 28. The striped section within the service area will be designated as a "no parking area/service turn around

- Waiver Requests

 1. Loading dock reduction from 6 to 1.

 2. Parking parage drive aiste width reduction from 26' to 24'.

 3. Column encroachment allowance into compact parking spaces within parking structure. A reduction in the width of the compact parking spaces from 8 feet to 7 feet when a column is located in the parking

LEGAL DESCRIPTION.
LOTS 1, 2, 3 AND 4, BLOCK 45, GENERAL MAP OF TAMPA,
ACCORDING TO THE MAP OR PLAT THEREOF IN PLAT BOOK 1, PAGE 7, PUBLIC RECORDS OF HILLSBOROUGH COUNTY,


REZONING REQUEST: CBD-1 TO CBD-2

SITE INFORMATION:

- 1. FOLIO NUMBERS:
- 193446.0000, 193445.0000, 193447.0000, 193448.0000
- 2 FLOOD PLAIN DATA:
 - COMMUNITY MAP PANEL NUMBER 120114 0024, FLOOD ZONE C


PLANNED DEVELOPMENT (PD) SITE PLAN





The developer grall utilize a structure that provides a recharged nethod of interminator pre treatment it at location to be determined prior to Constriction Plan appeared.

If the preferred stormwater connection of the project is to the translan street stormwater system, an analysis of the Ancheral integrity of the pope and operational consistion will have to be determined by the developer prior to Construction Plan approved. Such improvements, as determined by the analysis and approved by the Storm water Degartment, shall be compiled by the deseloper.



LEGEND:

FIRE HYDRANT



LANDSCAPE STREET TREE



SIDEWALK

--- PROPERTY BOUNDARY

BICYCLE PARKING RACK

BENCH

SITE DATA:

33 STORY BUILDING 24 STORY RESIDENTIAL 460 FEET MAXIMUM HEIGHT 502 RESIDENTIAL UNITS

14,500 SF RETAIL 508,736 GROSS FLOOR AREA

PARKING STRUCTURE SUMMARY LEVEL 2: 66 SPACES LEVEL 3: 92 SPACES

LEVEL 4: 95 SPACES LEVEL 6: 95 SPACES

LEVEL 7: 95 SPACES LEVEL 8: 95 SPACES LEVEL 9: 87 SPACES

TOTAL: 720 SPACES

PETITION # SIGNED LDC STAFF

SIGNATURES:

INTIALSEMP NO DATE CVO/1995 11/02/05 2/22/06 042047AL SCALE DESIGNED BY WOOD PARTNERS CVO/1995 11/02/05 1"=30" SITE PLAN CHECKED BY: PROJECT 610 FRANKLIN EXHIBIT B"05414-000-000

14,500 sq. ft.

1 space per 500

Farking Table:

One and Two Bedroom