



WASTEWATER TREATMENT PLANT

MEADOWOOD LOOP

SEGMENT 3:

2608 LF EXISTING 6" FORCE MAIN TO BE UPSIZED TO 8" ***CITY TO REIMBURSE 100% OF MATERIAL & INSTALLATION COST***

SEGMENT 1:

1700 LF EXISTING 6" FORCE MAIN TO BE UPSIZED TO 8" ***CITY TO REIMBURSE 100% OF MATERIAL & INSTALLATION COST***

TUCKER ROAD

SEGMENT 4:

2500 LF EXISTING 4" FORCE MAIN TO BE UPSIZED TO 6" ***CITY TO REIMBURSE 100% OF MATERIAL & INSTALLATION COST***

SEGMENT 2:

460 LF EXISTING 6" FORCE MAIN TO BE UPSIZED TO 8" ***CITY TO REIMBURSE 100% OF MATERIAL & INSTALLATION COST***

COPELAND DRIVE

SEGMENT 5:

2944 LF 12" WATER MAIN (8" REQUIRED, 12" REQUESTED BY CITY) ***CITY TO REIMBURSE 100% OF COST OF UPSIZING***

50 LF 6" FORCE MAIN STUB-OUT ***CITY TO REIMBURSE 100% OF MATERIAL & INSTALLATION COST***

CHANCEY ROAD

SEGMENT 6:

2235 LF 6" FORCE MAIN (4" REQUIRED, 6" REQUESTED BY CITY) ***CITY TO REIMBURSE 100% OF COST OF UPSIZING***

115 LF 8" WATER MAIN STUB-OUT. ***CITY TO REIMBURSE 100% OF MATERIAL & INSTALLATION COST***

T:\Projects\144-04_Guyon Parcel (Lennar)\Drawings\144-01-E05_Utility_Extension (Phase 2)\Current\Plan\14401E0505Utilities.dwg
1/11/2024 10:33:16 AM PLT OTTED BY: jack.cornwell

PROJECT NAME: CHANCEY 116 UTILITY EXTENSION		 505 E. JACKSON STREET SUITE 200 TAMPA, FLORIDA 33602 OFFICE: 813-375-0616 WWW.LEVELUPFLORIDA.COM
DRAWING TITLE: UTILITY EXTENSION PLAN		
PREPARED FOR: LENNAR		
PROJECT No.	144-01-E05	
SHEET	1 of 1	